

Addendum Number Two

To The Drawings and Specifications for
NEW FIRE STATION
City, State

Issued: Friday, February 25, 2005

"YOUR NAME" ARCHITECTS

1234 Street, Your City, Your State

NOTICE TO BIDDERS

You are hereby instructed to include in your bids the following changes and/or corrections to the Drawings and Specifications for Construction of the New Fire Station, City, State.

The additions and/or corrections shall be considered as a part of the Contract Documents as if incorporated therein. Where the following corrections and/or additions vary from the conditions of the Drawings and Specifications, such following changes or additions shall govern.

I. CHANGES TO THE SPECIFICATIONS:

1.1 BID DATE AND TIME (All Contracts):

The bid date shall be remain Thursday, April 14, 2005, times to receive the bids will remain as previously specified

1.2 Section 08200 – Wood Doors, Algoma Hardwood Inc is an approved supplier for the wood doors.

1.3 Section 08400 – Entrances & Storefronts;

- A. The finish of the aluminum doors, frames and window mullions shall be bronze to match the existing classroom windows.
- B. Paragraph 12, item C; the pressure plate shall be the standard square profile and installed on both the vertical and horizontal. Any reference to silicon glazing system shall be corrected to be equal to the standard Kawneer 1600 series or approved equal.

1.4 Section 08520 – Aluminum Windows; the finish of the aluminum classroom windows shall be bronze to match the existing.

II. CHANGES TO THE DRAWINGS:

2.1 Structural Drawings “S5” is not included or a part of the bid documents.

2.2 Sheet A04

- A. The expansion joint material shall be clarified to be located at the corridor connection to the new addition, for the full width of the corridor.
- B. The flooring in the corridor 100, shall be clarified to be carpet with a transition to rubber flooring at a line even with the corridor wall. The rubber flooring shall extend from this line (transition strip) to the stairs. The stair treads and risers are rubber, the lower landing and vestibule shall also be finished with rubber flooring. The upper landing of stair 102 (basement alternates) shall be finished in rubber. Storage closet 102 (Base Bid) the floor shall be finished with VCT.